



'Structwel' Plot No. 15, Sector 24,
Off Sion Panvel Highway,
Turbhe, Navi Mumbai-400705.

Tel. : 27841010 (7Lines)
Tel. Fax : 91-22-27841007
Customer Support : 9323376991/9323376992

E-mail : lab@structwel.com
Web : www.structwel.com

CHETAN R. RAIKAR

Chairman & Managing Director

CIN No.

U74210MH1978PTC020348

TEST REPORT NO. & DATE R&D/LAB/2014/SAN0068514/1689**03/07/2014**

1. Name & Address of Customer | M/s FOSROC CHEMICALS (INDIA) PVT. LTD.
1401/1402, 14th Floor, A-Wing, "The Great Eastern Summit",
Sec-15, CBD, Belapur, Navi Mumbai.
2. Project / Site | Self
3. Customer's Reference | E-mail Dtd.26/05/2014
4. Sample
- i) Description | Repair Mortar
- ii) Quantity | 06 Kg.
- iii) Date of receipt | 02/06/2014
- iv) Condition | Acceptable
5. Test method followed, if any | --
6. Date of Testing / Casting | 06/05/2014

TEST REPORT

1. Name of Sample : Fosroc Renderoc HSXtra
2. Name of Manufacture : M/s Fosroc Chemicals (India) Pvt. Ltd
3. Specimen Preparation :
- (a). Sample was prepared by adding water in received dry mortar.
The water was added in the dry sample as per manufacture's specification
Specification as follows :
W/p ratio - 0.16
- (b). Specimen size : 50 x 50 x 50 mm
- (c). Curing condition : Normal water bath curing.
4. Results

Sr. No.	Type of Test	Results
1.	Water Quantity for 25 kg. Sample (Ltr.)	4.00
2.	Flow Test (Sec)	--
3.	Setting Time (min)	
	1) Initial Setting Time	--
	2) Final Setting Time	--
4.	Pot Life (min)	--
5.	Compressive Strength (N/mm ²)	
	a) 1 days	--
	b) 3 days	--
	c) 7 days	59.07
	d) 28 days	81.89
6.	Flexural Strength (N/mm ²)	
	a) 7 days	--
	b) 28 days	--
7.	Tensile Strength (N/mm ²)	
	b) 7 days	--
	c) 28 days	--
8.	Wet Density (Kg/m ³)	--
9.	Dry Density (Kg/m ³)	--
10.	Bulk Density (Kg/Ltr)	--

NOTE :

- This certificate refers only to the sample submitted for testing.
- This certificate is valid at the time of and under the conditions specified herein.
- This certificate may not be reproduced in part, without the permission of this laboratory.
- Any correction invalidates this certificate.

Vinayak Samal
Vinayak Samal
Authorized Signatory

STRUCTWEL DESIGNERS & CONSULTANTS PVT. LTD.

'Structwel' Plot No. 15, Sector 24,
Off Sion Panvel Highway,
Turbhe, Navi Mumbai-400705.

Tel. : 27841010 (7Lines)
Tel. Fax : 91-22-27841007
Customer Support : 9323376991/9323376992

E-mail : lab@structwel.com
Web : www.structwel.com

**CHETAN R. RAIKAR**

Chairman & Managing Director

CIN No.

U74210MH1978PTC020348

INVOICE

Invoice No : SAN1415-01014				Invoice Date : 03-07-2014	
Customer Name : FOSROC CHEMICALS (INDIA) PVT. LTD. 1401/1402, 14th Floor, A-Wing, "The Great Eastern Summit", Sec-15, CBD, Belapur, Navi Mumbai.				Project/Site: Self Self	
Contractor Name :				Consultant Name :	
Customer's Ref : E-mail Dtd.26/05/2014				Inward No. : SAN0068514	
Sr. No	Name of Material/Test Name	Rate (Rs.)	Per	Qty. Recd.	Amount (Rs.)
1.	Concrete Physical Compressive Strength IS 516 - 1959	6500.00	Set	1	6500.00
Summary Of Payments					Sub Total 6500.00
UptoDate Balance .00				Service Tax(12.0%) 780.00	
Current Amount 7303.00				EC on ST(2.0%) 15.60	
Payments 7303.00				HEC on ST(1.0%) 7.80	
Net Balance .00				Total Payable Rs. 7303.00	
Authorised Signatory  For Structwel				Prepared By  (Seven Thousand Three Hundred and Three only)	
Service Tax Regd. No. AACCS2638FST001 Services Category: TECHNICAL INSPECTION AND CERTIFICATION Income Tax PAN AACCS2638F					